

3 022758

15-207.19545-00.00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019

NE,SE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.

3763 feet from south section line

575 feet from east section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS FeeFund

Name &amp; FEE FUND PLUGGING

Address

AB oil well X Gas Well SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICE, INC.

Lic. # 3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 28 Month: 6 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part None X

Operations Completed: Hour: 12:00P.M. Day: 28 Month: 6 2005

Actual Plugging Report: 600' OF 1" PIPE WAS FISHED FROM THIS WELL. A STUMP

OF 1" PIPE REMAINS IN THE 2" CASING AT 600'. 1" PIPE WAS RAN INTO THE 2" CASING TO

600'. CEMENT WAS PUMPE INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2"

CASING AT SURFACE. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 425'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

175 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.3) (THIS WELL WAS NO.2 ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

  
 TECHNICIAN

RECEIVED

JUL 11 2005

KCC WICHITA