

3 022756

15-207-19546-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019
SE,NE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.
4613 feet from south section line
485 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# BENNETT A NO.4
County ALLEN WOODSON

Name & FEE FUND PLUGGING
Address _____

Well Total Depth 750' feet
Production Pipe: 2" Size Feet 750'
Surface Casing: 8" Size Feet 20'

AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE, INC. Lic. # 3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 27 Month: 6 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____
TECHNICIAN
None

Operations Completed: Hour: 11:00A.M. Day: 27 Month: 6 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 700'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 350'. AT THAT DEPTH A SOLID OBSTRUCTION WAS ENCOUNTERED. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 94 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.4) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
JUL 11 2005
KCC WICHITA

Bu