

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-23008-00-01

Spot: SENESW

Sec/Twnshp/Rge: 27-34S-10E

1485 feet from S Section Line, 2805 feet from E Section Line

Lease Name: BUCHELE

Well #: 1

County: CHAUTAUQUA

Total Vertical Depth: 1780 feet

Operator License No.: 6433

Op Name: BUCK, PAUL JORDAN

Address: PO BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1779		
SURF	7	200		
T1	2.375	1490		

\$57⁸⁵

Well Type: EOR

UIC Docket No: E22270.2

Date/Time to Plug: 06/08/2005 8:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S INC.

Proposal Rcvd. from: JOHN ELMORE

Company: ELMORES, INC.

Phone: (620) 249-2519

Proposed
Plugging
Method:

TO RUN 1" INSIDE 4.5" CASING & PUMP CEMENT FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE

WitnessType: PARTIAL

Date/Time Plugging Completed: 06/08/2005 5:00 PM

KCC Agent: RON ROWE

Actual Plugging Report:

Perfs:

RAN 1" HYDRIL INSIDE 4.5" CASING TO 1250' & GELLED HOLE, THEN PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" UP TO 500' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" & TOPPED-OFF WELL. USED TOTAL OF 63 SACKS CEMENT & 2 SACKS GEL.

RECEIVED
KCC DISTRICT #3

AUG 9 2005

CHANUTE, KS

RR

Remarks: PLUGGED UIC WELL.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED
AUG 17 2005
KCC WICHITA

INVOICE
DATE 8-17-05
INV. NO. 2006060326