

KANSAS

af
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20255-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1970
CONSERVATION DIVISION
Wichita, Kansas
7-29-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers.

Complete Address Shields Building, Russell, Kansas.

Lease Name C. A. Camp Well No. 1

Location NE-NE-SW Sec. 7 Twp. 6 Rge. (E) (W) 29

County Sheridan Total Depth 4158'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated.

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 6:30 AM Day 25 Month 6 Year 1970

The above well was plugged as follows:

272'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1425'.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 100 Sx. cement thru
DP from 1650' to 1325'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 6/30/70
INV. NO. 2139-W