

KANSAS

Form CP-3  
Rev. 6-26-62

*SL*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20015-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 9 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
5-9-69

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas

Lease Name Barnett Well No. A-2

Location CSW-NE Sec. 17 Twp. 6 Rge. (E) (W) 31

County Thomas Total Depth 4480'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 4:30AM Day 2 Month 5 Year 1969

The Above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 160 Sx.

Circulated hole with heavy mud. Pulled DP to 1850' and displaced 100 Sx. cement thru

DP from 1850' to 1525'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from

240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/9/69

INV. NO. 9235-11

Signed: M. S. Nichols  
Well Plugging Supervisor