

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-193-20,179-00-00 (of this well)

Operator's Full Name Nelson Petroleum Co.

Complete Address 2301 4th National Bk. Bldg., Tulsa, Okla.

Lease Name Vernon Deckert Well No. 1

Location NW SE NE Sec. 15 Twp. 6 Rge. (E) (W) 31

County Thomas Total Depth 4600'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Abercrombie Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 6:30 P Day 12 Month 12 Year 1978

The above well was plugged as follows:

RTD 4600' 8 5/8 csg set 346' cwc Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 1600' thru drill pipe.

Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 14 1978

CONSERVATION DIVISION  
Wichita, Kansas

12-14-78

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-14-78  
IN. NO. 8750-W

Signed: Geo. Mussey  
Well Plugging Supervisor