

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20016-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1969
CONSERVATION DIVISION
Wichita, Kansas
5-13-69

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name Nichols Well No. 1

Location CSW-NE Sec. 8 Twp. 6 Rge. (E) (W) 31

County Thomas Total Depth 4240'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 11:00AM Day 11 Month 5 Year 1969

The Above well was plugged as follows:

256'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1575'.

Circulated hole with heavy mud. Pulled DP to 1800' and displaced 100 Sx. cement thru
DP from 1800' to 1475'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 210'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dinkel
Well Plugging Supervisor

DATE 5/14/69
INV. NO. 9750-W