

DISTRICT CONSERVATION AGENT'S REPORT

15-163-00217-00-00



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 121-12

LOCATION SW SW NW

SEC. 28 TWP. 7S RGE. 16W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Fred E. Jones

Operator W. P. Faulkner & Pickrell Drlg. Co., Inc. Address 705 Fourth Nat'l. Bank Bldg., Wichita, Kans.

Field _____ County HOOKS

Total Depth 3315 Feet.

(Describe briefly the manner in which the well was plugged)

35 jts. 8-5/8" 2 1/4# smls. casing set at 1080' in a 12 1/4" hole,

cemented with 500 sacks bulk cement, Halliburton process. Drilled 7-7/8"

hole from 1080' to 3315' T.D. No oil string run.

Filled hole with heavy mud from 3315 to 1080'. Set bridge and run 15

sacks cement. Fill with mud to 550' and bridge hole and run 15 sacks

cement. Fill with mud to 30', bridge hole and run cement to bottom of

cellar.

District Conservation Agent

Date October 25, 1949

11-10-49

PLUGGING
FILE SEC. 28 T. 7 R. 16W
BOOK PAGE 121 LINE 12