

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20498-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1974
4-4-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Inc.
Complete Address P. O. Box 922, Hreat Bend, Kansas 67530
Lease Name Hardman "A" Well No. 1
Location NE SW SE Sec. 27 Twp. 7 Rge. (E) (W) 16
County Rooks Total Depth 3301'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Midway Drilling, Inc.

Address Great Bend, Kansas License No. 620
Operation Completed: Hour 11 A Day 1 Month 4 Year 1974

The above well was plugged as follows:

Total Depth 3301' 8 5/8 csg set at 209' cwc 150 sk.
4 1/2 csg set at 2723' cw 75 sk cem.
4 1/2 csg PBDT 2685' Perf. (2606-2610)
Filled 4 1/2 csg W/sd (2590-2685) dumped 3 sk cem W/dump bailer. (2560-2590)
Cutoff and recovered 2000' of 4 1/2 csg.
Pumped down 8 5/8 csg with 18 sk gel & water -200 lbs hulls -70 sk cem. -8 sk gel
& water -released 8 5/8 plug and pumped 50 sk cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 4/4/74
INV. NO. 8886-W