



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20496-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAR 27 1975
3-27-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name George R. Joy

Complete Address 204 E. 28th St., Hays, Kansas 67601

Lease Name Stackhouse Well No. 1

Location 50' N of SE^{NW} SW Sec. 27 Twp. 7 Rge. (E) (W) 16

County Rooks Total Depth 2864'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Crowe Casing Pulling

Address Box 706, Hays, Kansas 67601 License No. 733

Operation Completed: Hour 10:30 A Day 21 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 2864' 8 5/8 csg 205' cwc 175 sk.

4 1/2 csg 2801' cw 50 sk cem.

Filled 4 1/2 csg W/snd (2864-2775') dumped 3 sk cem W/dump bailer. (2775-2745)

Cutoff & recov. A/2000' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -80 sk poz

60-40 -8 sk gel & water -released plug & 60 sk poz 60-40 by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 4/1/75

IV. NO. 1075-W