

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20031-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1970
CONSERVATION DIVISION
Wichita, Kansas
6-29-70

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center Building, Wichita, Kansas.

Lease Name Dean Well No. 1

Location CNE-NE Sec. 21 Twp. 6 Rge. (E) (W) 32

County Thomas Total Depth 4640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 1425 Wichita Plaza Building Wichita, Kansas. License No.

Operation Completed: Hour 9:30 AM Day 26 Month 6 Year 1970

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1500'.

Circulated hole with heavy mud. Pulled DP to 1725' and displaced 100 Sx. cement thru
DP from 1725' to 1400'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 6/30/70
INV. NO. 2138-W