

15-179-05584-00-00

~~KANSAS~~

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Continental Oil Company,
Complete Address 3535NW 58th Street, Oklahoma City, Oklahoma.
Lease Name Adell L-KC Unit Well No. 205
Location SW-SW-NW Sec. 12 Twp. 6 Rge. (E) (W) 27
County Sheridan Total Depth 3870'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Pipe Pullers, Incorporated,
Address Box #186, Ellinwood, Kansas. License No. 462
Operation Completed: Hour 5:00 PM Day 2 Month 12 Year 1974

The above well was plugged as follows:

244'--10 3/4" Surface casing, cement circulated with 300 Sx.
3869'--7" OD Production casing cemented on bottom with 300 Sx. Well plugged back to
3850'. Top of perforations from 3638'.
Pushed plug to 3630', sanded back to 3590' and set 6 Sx. cement with dump bailer.
Pulled 7" casing and squeezed well initially with 5 sacks hulls and 17 sacks gel
following with 135 Cu. Ft. cement from 1325' to 1000' then 22 sacks gel from 1000'
to 260' and followed with 40 Cu. Ft. cement from 260' to 180' then 6 sacks gel from
180' to 30' and finally 15 Cu. Ft. cement from 30' to base of cellar. Maximum pump-
in pressure-150#. FSIP-100#. (Mudding and cementing by Sun Oil Well Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/10/74
INV. NO. 432-w