

15163-01064-0001

Form CP-3  
Rev. 6-26-62

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Don E. Pratt

Complete Address: Box 370 Hays, Kansas

Lease Name Crowe Well No. 1

Location NE NE NW Sec. 20 Twp. 7 Rge. 19 (E) (W) X

County Rooks Total Depth 3452

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas Box 405 License No. 436

Operation Completed: Hour 12:30 P Day 9 Month 9 Year 1967

The Above well was plugged as follows:

RTD 3452' 8 5/8 csg set at 217' cwc

5 1/2 csg set at 3442' cw 75 sc cement.

PB 3430 - Poured 10' sand and dumped 5 sc cement with dump bailer

Recov. 1893' off 5 1/2 csg.

Squeezed thru 8 5/8 plg container with 30 sc gel and 135 sc cement.

Gel from TD to 700 cement 200-700 gel 50-200 and cement 0-50.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 11 1967  
9/11/67

CONSERVATION DIVISION

I hereby certify that the above well was plugged as herein stated. Wichita, Kansas

INVOICED  
DATE 9/12/67  
INV. NO. 6293-W

Signed: Geo A. Murray  
Well Plugging Supervisor