

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163-21071-00-00 *R*

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name JAY BAYER

Complete Address BOX 6 - CODELL, KANS. 67630

Lease Name SARVER Well No. #1

Location NE-NE-NE Sec. 19 Twp. 7^s Rge. 16^w (East) (West)

County ROOFS. Total Depth 3250 *FE*

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor BAYER WELC SERVICE

Address BOX 6 - CODELL, KANS. License No. IN PROCESS OF GETTING ONE.

Operation Completed: Hour: 11:30 *AM* Day: 9th Month: DEC. Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" - 1076^{FE} SP. CUL. w/ 450ST CNT. -> 4 1/2" SET @ 3109^{FE} w/ 125ST CNT.
PLUG. BACK. T.D. 2650^{FE} -> PERFS. 2629^{FE} - 30^{FE} SAND BOTTOM TO 2570^{FE} w/ 1/2ST CNT.
SHOT CASING @ 2200^{FE} + 2000^{FE} RECOVERED 2000^{FE}
ORDERED 140ST 50% Fozmin 4% GEL. 3% CA-CL -> 17ST GEL. 5ST HULL'S
AND 8 5/8" PLUG. -> PUMPED IN WITH PUMP. TRUCK.
PUMPED IN 4ST HULL'S -> 12ST GEL. -> 2ST HULL'S -> 40ST CNT.
5ST GEL. -> RELEASED PLUG. AND 40ST CNT. -> MAX. PRESSURE 450^{PSI}
CEMENTED BY ALLIED CNT.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1-21-82
INV. NO. 9035-W

RECEIVED
SIGNED: Maurice Schmidt
Conservation Division Agent
CONSERVATION DIVISION
Wichita, Kansas
12-14-81