

4-031959

6-28

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,465 - 00-00

SE SE NW /4 SEC. 28, 07 S, 16 W
2970 feet from S section line
2970 feet from E section line

Operator license# 5242 Lease Jones well # A-4

Operator: Petroleum Management, Inc. County Rooks

Address: 14201 E. Central Wichita, Kansas 67230
Well total depth 3217 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 216 feet

104.55

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 28 Month: June Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing Pulling Phone:

Were: Order 200 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Order sand and common cement - 5 sxs.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:30 P.M., Day: 28, Month: June, Year: 94

Actual plugging report: 8 5/8" set @ 216' w/150 sxs. cwc. 5 1/2" set @ 3179' w/200 sxs. P.B.T.D. 3165'. Prod. perms. 2834' - 3020'. B.P. @ 2950' well was squeezed record not available. Sand back to 2780' w/5 sxs. common cement on sand with bailer. Shot @ 1800' tight - shot @ 1200' tight - mix and pump 20 sxs. cement blend with hulls. Displace to 800' with 1000# P.S.I. Shot @ 700' tight - shot @ 530'. Pipe free. Pulled to 350' mix and pumped 80 sxs cement blend with hulls - circulated to surface. Pulled pipe topped off with 20 sxs. cement blend. Used total 120 sxs. cement blend w/500# hulls. Mixed in w/1000# P.S.I on casing. Before circulation. Plug complete.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
AUG 1 8 1994
P-12-24

Remarks: Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I [X] did not observe the plugging. Carl Goodrow

INVOICED
DATE 8-24-94
INV. NO. 40965

(agent)
Form CP-2/3