

4-031951

7-11 D-16,915

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-20,460

~~00-00~~  
02

NW SE NE /4 SEC. 28, 07 S, 16 W  
3630 feet from S section line  
990 feet from E section line

Operator license# 5242 Lease Jones "B" well # 2

Operator: Petroleum Management, Inc. County Rooks

Address: 14201 E. Central Well total depth 3240 feet  
Wichita, Kansas 67230 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 827 feet

105.30

Aband. oil well \_\_, Gas well \_\_, Input well \_\_, SWD X, D & A \_\_

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 11 Month: July Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing Pulling, Inc. Phone: \_\_\_\_\_

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 8:00P.M., Day: 11, Month: July, Year: 1994

Actual plugging report: 8 5/8" set @ 827' w/325 sxs. cwc. 5 1/2" set @  
3232' w/200 sxs. PBTD 3190'. Prod. perfs. 2724' - 2874'. Sand back to  
2670' w/5 sxs. common cement on sand with bailer. Shot free at 1800'  
and 1150'. Pipe parted @ 1300' - mixed and pumped 80 sxs. cement blend  
to 1167'. Pulled pipe to 500' - circulated cement with 120 sxs. cement  
blend. Pulled 5 1/2" casing. Topped off 8 5/8" with 30 sxs. cement  
blend. Used total of 230 sxs. cement blend with 500# hulls mixed in.  
Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy. plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: \_\_\_\_\_ GL

I did  and not  observe the plugging. Carl Goodrow

**INVOICED**  
DATE 7-26-94  
INV. NO. 40890

HD

RECEIVED  
(agent) STATE CORPORATION COMMISS  
Form CP-2/3 7-22-94  
**JUL 22 1994**