

4-050145

9-1

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,452

SE SW NE /4 SEC. 28, 07 S, 16 W
2970 feet from S section line
1650 feet from E section line

Operator license# 5242

Lease Jones "A" well # 1

Operator: Petroleum Management, Inc.

County Rooks

109.52

Address: P.O. Box H
Plainville, Kansas 67663

Well total depth 3370 feet 5 1/2 @ 3266'
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing - Plainville Well Service License#

Address: Box 31 - Russell, Kansas - Plainville, Kansas 67663

Company to plug at: Hour: Noon Day: 1 Month: September Year: 94

Plugging proposal received from: Don Keener

Company: Petroleum Management, Inc. Phone: 913-434-2042

Were: Mill to or near the anhydrite - spot full of common cement and pressure up with 60/40 pozmix - 6% gel. I will be there in P.M. Tubing had been pulled.

Plugging Proposal Received by: Don Butcher
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:20P.M., Day: 1, Month: September, Year: 94

Actual plugging report: Milled and worked tubing to 870' (SIC) or 50' below the base of the Cedar Hills Sandstone. Spotted 100 sxs. common cement pulled tubing and pressured 150 sxs. of 60/40 pozmix - 6% gel to 400# P.S.I. Standing pressure 100#. Backside of 5 1/2" casing. Would not take cement. 350 sxs. of cement should or could have filled over 3000' of 5 1/2" casing.

STATE CORPORATION COMMISSION

OCT 20 1994

Remarks: Anhydrite (stone corral) at 1140' - casing full of holes.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 1840 GL

I did X observe the plugging.

Don Butcher
(agent)

INVOICED
DATE OCT 21 1994
INV. NO. 414