

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,251-00-00

SW $\frac{1}{4}$, Sec. 6, T 7 S, R 16 W $\frac{1}{2}$
1514 feet from N $\frac{1}{2}$ section line
212 feet from $\frac{1}{2}$ E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5716

Lease Name Fenton Well # 1

Operator: S & I Oil Co.
Name & El Dorado, Ks. 67042
Address

County Rooks

Well Total Depth 3410 feet 110.82
Conductor Pipe: Size feet
Surface Casing: Size $8\frac{5}{8}$ feet 1264 - 400 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Co. License Number 8241

Address Box 506, Russell, Kansas

Company to plug at: Hour: 8:40 AM Day: 10 Month: February Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO

(company name) (phone)

were: Order 150 sks. 50/50 poz mix 6% gel, 3% c.c. $8\frac{5}{8}$ plug. Jett pitts and circulate hole with heavy mud between all plugs.

1st plug 1250' @ 20 sks. cement

2nd plug 900' @ 100 sks. 3rd plug 40" @ 10 sks. $8\frac{5}{8}$ " plug $\frac{1}{2}$ sk hulls and

10 sks cement. Cementing to base of cellar

10 sks. in Rat Hole - 10 sks. in Mouse Hole

Signed *Gilbert P. Leiker*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8PM. Day: 10 Month: February Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 1250' w/20 sks

2nd plug @ 1900' w/100 sks

3rd plug @ 40' w/10 sks.

10 sks in Rat Hole 10 sks. in Mouse Hole

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Cementing Company: Allied Cementing Company

FEB 21 1984

CONSERVATION DIVISION
Wichita, Kansas

2-21-84

I hereby certify that the above plugging instructions were given as herein stated and that I (did not observe this plugging.

Signed *Gilbert P. Leiker*
(TECHNICIAN)

INVOICED

DATE 2-22-84

INV. NO. 0307

FORM CP-2/3
Rev. 9-82