

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15-193-2094-0000 (of this well)
Lease Owner Halliburton Oil Producing Company
Address 2915 Classen Boulevard, Oklahoma City, Oklahoma
Lease (Farm Name) DECHERT Well No. 1
Well Location C SW SW Sec. 17 Twp. 6 Rge. 31 (E) (W) X
County Thomas Total Depth 4630' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 11:00 p.m., 12-07-79

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Gerrell Veatch Address 1207 Court Place, Colby, Kansas

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Halliburton Oil Producing Company 12-13-79

Address 2915 Classen Boulevard, Oklahoma City, Oklahoma

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent

Date: December 12, 1979

15-193-20194-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Halliburton Oil Producing Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Dechert #1
 LOCATION: C SW SW, Section 17-6-31,
 Thomas County, Kansas
 SPUD DATE: November 30, 1979
 COMPLETION DATE: December 07, 1979

0	330	Surface soil, sand and shale
330	1050	Shale
1050	2286	Shale and sand
2286	2671	Shale
2671	2710	Anhydrite
2710	3119	Shale and sand
3119	3765	Lime and shale
3765	4357	Lime
4357	4422	Lime and shale
4422	4518	Lime
4518	4620	Lime and shale
4620	4630	Lime
	4630	Rotary Total Depth

SAMPLE TOPS:

Anhydrite 2671'
 B/Anhydrite 2710'

Spud hole at 11:45 a.m., November 30, 1979. Drilled 330' of 12 1/4" hole. Ran 9 joints of 8-5/8" - 20# casing. (Talley 322') Set at 329' K.B. with 235 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 4:45 p.m., November 30, 1979.

T.D. 4630'. Set 1st plug at 1550' with 70 sacks, 2nd plug at 320' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks and 5 sacks in the rathol. Cemented with 50/50 posmix, 6% gel. Plug was down at 11:00 p.m., December 07, 1979.

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

DEC 12 1979
 12-13-79

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Dechert #1, C SW SW, Section 17-6-31, Thomas County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 12th day of December, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.

State of Kansas



15-193-20194-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY

Governor
Chairman
Commissioner
Commissioner

Carol J. Larson, Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

December 18, 1979

WELL PLUGGING AUTHORITY

Well No. 1
Lease Dechert
Description C SW SW
Section 17-6S-31S
County Thomas
Total Depth 4630'
Plugging Contractor Abercrombie Drig.Inc.

Halliburton Oil Producing Company
2915 Classen Blvd., Suite 300
Oklahoma City, Oklahoma 73106

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,

J. Lewis Brock,
Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Palco, Kansas 67657 is hereby assigned to supervise the plugging of the above named well.