

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM
File One Copy

DEC 22 1978
12-22-78
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 193 - 20,179-0000 (of this well)
Lease Owner Nelson Petroleum Company
Address 2301 Fourth National Bank Bldg, Tulsa, Oklahoma 74119
Lease (Farm Name) Vernon Deckert Well No. 1
Well Location NW SE NE Sec. 15 Twp. 6S Rge. 31W (E) (W) X
County Thomas Total Depth 4600' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 6:00 p.m., 12-12-78

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 So. 2nd St., Hill City, Kansas

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Nelson Petroleum Company

Address 2301 Fourth National Bank Bldg., Tulsa, Oklahoma 74119

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent

Jack L. Partridge

Date: December 20, 1978

CONTRACTOR'S WELL LOG

OPERATOR: Nelson Petroleum Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Vernon Deckert #1
 LOCATION: NW SE NE, Section 15-6S-31W
 Thomas County, Kansas
 SPUD DATE: December 1, 1978
 COMPLETION DATE: December 12, 1978

0	348	Surface soil, sand & shale
348	950	Shale
950	2288	Shale and sand
2288	2635	Shale
2635	2675	Anhydrite
2675	2875	Shale
2875	3807	Lime and shale
3807	4069	Lime
4069	4228	Lime and shale
4228	4295	Lime
4295	4435	Lime and shale
4435	4600	Lime
	4600	Rotary Total Depth

Spud hole at 5:30 p.m., December 1, 1978. Drilled 348' of 12 1/4" hole. Ran 8 joints of 8-5/8" - 28# used casing. Set at 346' with 225 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 12:30 a.m., December 2, 1978.

T.D. 4600'. Set 1st plug at 1600' with 70 sacks, 2nd plug at 300' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 6:00 p.m., December 12, 1978.

SAMPLE TOPS:

Anhydrite 2635'
 B/Anhydrite 2675'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)


RECEIVED
 STATE CORPORATION COMMISSION
 DEC 22 1978
 12-22-78
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Vernon Deckert #1, NW SE NE, Section 15-6S-31W, Thomas County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 20th day of December, 1978.



Sherrie L. Brooks
 Sherrie L. Brooks, Notary Public

My commission expires 8-21-82



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

December 14, 1978

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Vernon Deckert
Description	NW SE NE Sec. 15-6-31W
County	Thomas
Total Depth	4600
Plugging Contractor	Abercrombie Drilling


Nelson Petroleum Co.
2301 Fourth National Bank Building
Tulsa, Oklahoma 74119

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Leo Massey, 109 West 15th, Hays, Kansas 67601
is hereby assigned to supervise the plugging of the above
named well.