

15-193-20016-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Thomas County. Sec. 8 Twp. 6S Rge. (E)31 (W)

Location as "NE/CNW%SW%" or footage from lines C SW NE

Lease Owner Rains & Williamson Oil Co., Inc.

Lease Name NICHOLS Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-11 19 69

Application for plugging filed 5-11 19 69

Application for plugging approved 5-11 19 69


Plugging commenced 5-11 19 69

Plugging completed 11 AM 5-11 19 69

Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.

If a producing well is abandoned, date of last production -- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas

Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4240 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	257'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud. Spotted 70 sacks GL-3 (6% gel), at 1800'.
Pulled up to 270'. Spotted 20 sacks same. Set solid bridge
at 40' with 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1969
CONSERVATION DIVISION
Wichita, Kansas

5-15-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

Address 1425 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.


Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14 day of May 19 69

Sherry Gish
Sherry Gish Notary Public.

My commission expires 6-30-71



15-193-20016-0000

ROTARY DRILLING LOG

Operator: Rains & Williamson
Oil Co., Inc.
NICHOLS #1
C SW NE 8-6S-31W
Thomas County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 5-2-69
Completed: 5-11-69
Casing: 8-5/8"/257'/160 sacks

Formations

Surface Clay and Sand	190'
Blue Shale	258'
Shale	2334'
Blaine Anhydrite	2347'
Shale	2412'
Anhydrite	2428'
Shale and Red Bed	2630'
Red Bed	2652'
Anhydrite	2691'
Shale and Red Bed	2800'
Shale	3480'
Shale and Lime	3835'
Lime	4240'
Rotary Total Depth (D&A)	4240'

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1969
CONSERVATION DIVISION
Wichita, Kansas
5-15-69

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 14th day of May, 1969.


Sherry Gish Notary Public

My Commission Expires:
6-30-71

