

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

			X

Locate well correctly on above
Section Plat

Thomas County, Sec. 23 Twp. 6S Rge. (E) 32 (W)
Location as "NE/CNW%SW%" or footage from lines C SE/4 SE/4
Lease Owner Target Drilling Corporation
Lease Name Akers Well No. 1
Office Address 910 Enterprise Bldg Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/4 1961
Application for plugging filed 3/4 1961
Application for plugging approved 3/4 1961
Plugging commenced 3/4 1961
Plugging completed 3/5 1961
Reason for abandonment of well or producing formation f No productive horizons encountered.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fabricus, Hill City, Kansas
Producing formation None Depth to top x Bottom x Total Depth of Well 4704 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Water Sand	Fresh Water	179	200'	8 5/8"	236'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set cement plug at 400 feet with twenty sacks of cement, filled hole with mud to 230' and set cement plug with 20 sacks of cement, filled hole with mud to 40' from surface, set plug with ten sacks of cement with two wires attached to plug and extending to surface.

RECEIVED
STATE CORPORATION COMMISSION

MAR 2 1961

CONSERVATION DIVISION
Wichita, Kansas

3-9-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Target Drilling Corporation
Address 910 Enterprise Building

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
J. W. Genzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Genzer
910 Enterprise Building, Tulsa 3, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1961

My commission expires Nov. 13, 1963
Karel Keenan Notary Public.



TARGET DRILLING CORPORATION

Akers No 1 - C SE SE -23 - 6S - 32W
Thomas County Kansas

15-193-30002-00-00

DRILLERS LOG

- 0-255 Sand and shale
- 255-1354 Shale
- 3154-1600 Shale and lime
- 1600-1945 Lime and shale and sand
- 1945-2699 Shale and lime
- 2699-2853 Shale and red beds
- 2853-3203 Shale and lime
- 3203-3402 Shale and red beds
- 3402-3814 Shale and lime
- 3814-4188 Lime
- 4188-4363 Shale and lime
- 4364-4487 Lime
- 4487-4625 Shale and lime
- 4625-4683 Lime
- 4683-4704 Lime and shale
- T.D.

RECEIVED
STATE COMMISSION

MAR 9 1961

CONSERVATION DIVISION
Tulsa, Kansas

3-9-61

C. S. Cannan

C. S. Cannan

State of Oklahoma)
County of Tulsa)

Subscribed and sworn to me a Notary Public this 8th
day of March, 1961.

John W. Caldwell

Notary Public

My Commission expires July 22, 1963.

C. S. (STAN) CANNAN, CONSULTING GEOLOGIST, TULSA, OKLA.