

15-193-00006-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas


WELL PLUGGING RECORD

THOMAS.

County. Sec. 14 Twp. 6 Rge. 32 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW/ SW/ SW/  
Lease Owner Jackson, Shear and Parker  
Lease Name Jackson, shear & Parker-B.B. Foster Well No. 1  
Office Address \_\_\_\_\_  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced August 5 1958  
Plugging completed Aug 9, 1958  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4770 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4770 feet to surface feet for each plug set.

Hole filled with sand from 4770 to 4358. (Casing preforated at 4368)  
Four sacks of cement placed in hole with dump bailer, pipe then pulled  
and hole filled with mud to five hundred feet; ten foot rock bridge  
installed between 500 ft and 490 ft and 25 sacks of cement poured in hole;  
Hole then filled with mud to forty feet, where rock bridge installed between  
40 and 30 ft; hole capped with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1958  
CONSERVATION DIVISION  
Wichita, Kansas  
5-18-58

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Barnes and Sons Pipe Pulling Co.,  
Address Russell, Kansas.

STATE OF Oklahoma, COUNTY OF Stephens, ss.  
Miles Jackson, Operator (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Miles Jackson  
Box 149, Duncan, Okla.  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1958  
David Gray Notary Public.

My commission expires June 26, 1962

PLUGGING  
FILE SEC. 14 T. 6 R. 32W  
BOOK PAGE 123 LINE 30

15-193-00006-00-00

JACKSON, SHEAR & PARKER  
BOX 149  
DUNCAN, OKLAHOMA

RECORDED IN THE OFFICE OF THE COUNTY CLERK OF THE COUNTY OF...

DRILLERS LOG

Foster No. 1

SW $\frac{1}{4}$ -SW $\frac{1}{4}$ -SW $\frac{1}{4}$  Sec. 14, T6-S, R-32W,  
Thomas County, Kansas

Rig #

Lease

0	40	Surface soil & clay	3210	3360	Shale
40	290	Sand & shale	3360	3570	Lime & shale
290	312	Shale	3570	3660	Lime & shale
312	1740	Shale & shells	3660	3710	Broken lime
1740	2030	Shale & sandy lime	3710	3820	Lime
2030	2180	Shale & shells	3820	3915	Lime & shale
2180	2240	Shells & sand	3915	3980	Lime
2240	2310	Shale & lime	3980	4040	Lime & shale
2310	2338	Shale & lime	4040	4055	Lime
2338	2673	Shale & lime	4055	4098	Lime
2673	2705	Anahydrate	4098	4238	Lime
2705	2800	Lime & shale	4238	4376	Lime & shale
2800	2885	Lime & shale	4376	4495	Lime & shale
2885	3115	Lime & shale	4495	4575	Lime & shale
3115	3210	Broken lime	4575	4770	Lime

I certify the above to be a true and exact copy of the  
Drillers Log as shown by the Daily Drilling Reports.

BADGER DRILLERS, INC.

Fred A. Heil

Subscribed and sworn to before me

this 1st day of August, 1958.

Notary Public Martha Meeker  
My Commission Expires 6-26-60.

PLUGGING  
FILE SEC. 14 T. 6 R. 32W  
BOOK PAGE 123 LINE 30

RECORDED  
INDEXED  
AUG 18 1958  
8-18-58