

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20,467 ⁰⁰⁻⁰⁰

LEASE NAME Jones

WELL NUMBER "B" #3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 28 TWP. 7 RGE. 16W (E) or (W)

COUNTY Rooks

Date Well Completed

Plugging Commenced 6-30-94

Plugging Completed 7-01-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Management Inc.

ADDRESS P. O. Box H Plainville, KS 67663

PHONE# (913) 434-2042 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3320'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	975'	none
				5 1/2	2950'	1809'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded off bottom @ 2776' & ran 5 sks cement. Shot @ 2019' & 1809', pipe came loose. Pulled pipe up to 1100', spotted 80 sks and 300# hulls. Pulled pipe to 500', spotted 75 sks and 200# hulls, circulated to surface. Pulled out rest of pipe, topped off with 20 sks cement. 60/40 poz 10% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6080

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 6th day of July, 19 94

Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
JUL 07 1994
7-7-94
CONSERVATION DIVISION
Wichita, Kansas