

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-20,464 ²⁰⁻⁰⁰

LEASE NAME Jones

WELL NUMBER "A" #3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

990 N Ft. from S Section Line

2310 W Ft. from E Section Line

SEC. 28 TWP. 7 RGE. 16W (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 6-21-94

Plugging Completed 6-22-94

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS P. O. Box H Plainville, KS 67663

PHONE# (913) 434-2042 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	935'	none
				5 1/2	3359'	2000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Sanded off bottom @ 2775' & dumped 5 sks cement. Shot well @ 2300, 2200 & 2000 - pipe came loose. Pulled up to 1100, pumped 100 sks cement w/300# hulls. Pulled up to 500, pumped 120 sks cement & circulated to surface. Pulled rest of pipe, topped off with 500# gel. 60/40 poz 10% gel. Plugging complete.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License _____

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) o


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 30th day of June, 19 94

My Commission Expires: _____



Notary Public