

15-163-00354-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 21 Twp. 7 Rge. 16W (E) (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner A.F. Keating
Lease Name Sayles Well No. 1
Office Address Natl. Bank Of Tulsa Bldg. Tulsa Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 30 - 1952
Application for plugging filed October 31 - 1952
Application for plugging approved October 31 - 1952
Plugging commenced 12 Noon October 31 - 1952
Plugging completed 1 P.M. October 31 - 1952
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3360 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Run 164 Ft. 10 3/4" - 32 Lb. Csg In 13 3/4" Hole Cemented With 100 sacks regular cement Circulated					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Swedged 10 3/4" surface to 2" Pumped 100 Sacks cement in surface pipe
Let Cement stand at ground level
Cemented with Sun Cementing Co. Truck

NOV - 5 1952
CONSERVATION DIVISION
Wichita, Kansas

11-5-52

Name of Plugging Contractor Co. Tools And Sun Cementing Co.
Address Hays Kansas

STATE OF Kansas, COUNTY OF Graham, ss.
Hugh Brittain - Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Hugh Brittain
Box 585 Nice City Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 52

My commission expires March 5, 1954
Bryan B. Parker Notary Public.

24-2675-S 2-52-20M

PLUGGING
FILE SEC 21 T 7 R 16W
BOOK PAGE 57 LINE 3

15-163-00354-00-00

Company KEATING DRILLING CO. (510 Natl. Bank of Tulsa Bldg., Tulsa 3, Okla).

Farm SAYLES Well No. 1 Loc. NE NE SW 21-7-16W

TD 3360' County ROOKS, KANS.

Comm 10/19/52 Comp 10/31/52 Prod D&A

Contractor KEATING DRLG CO Elev 1769 KB

Csg 166' 10 3/4" Time Log Geolograph
Elec Log Schlumberger

0- 180 surface sd & clay
 180- 400 shale & shells
 400- 540 sand
 540- 660 red bed
 660- 665 pyrites
 665- 790 sand
 790-1085 red bed, lime, shale
 1085-1107 anhydrite
 1107-1440 shale
 1440-1605 shale & lime
 1605-1865 lime & shale
 1865-1944 bkn. lime & shale
 1944-2000 lime
 2000-2210 lime & shale
 2210-2465 shale & lime
 2465-2645 lime & shale
 2645-3268 lime & shale
 3268-3326 shale & lime (Arb 3315)
 3326-3360 lime & shale
 TD 3360

Geol. Tops	
Anhydrite	1086
Topeka	2676
Heebner	2894
Toronto	2918
L-KC	2939
B/KC	3196
Conglomerate	3307
Arbuckle	3316
TD	3360

STATE OF KANSAS, COUNTY OF SEDGWICK SS:


Dale Martin, representative of operator of above described well, being first duly sworn on oath, states: That I have knowledge of the facts, statements and matters herein contained, and the log of the above well as filed, and the same is true and correct. So help me God.

Signature Dale Martin
836 Marcilene, Wichita 17, Kans

Subscribed and sworn to before me this 7th day of November, 1952.

My commission expires October 17, 1953

Dorothy M. Barber
Notary Public



PLUGGING
FILE SEC 21 T 7 R 1624
BOOK PAGE 57 LINE 3

RECEIVED
CORPORATION COMMISSION
NOV - 8 1952 11-8-52
CONSERVATION DIVISION
Wichita, Kansas