

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21408-00-00
Spot: S2SWNW Sec/Twnshp/Rge: 11-25S-9W
2955 feet from S Section Line, 4747 feet from E Section Line
Lease Name: TERRILL OCHS A Well #: 1
County: RENO Total Vertical Depth: 4585 feet

Operator License No.: 5585
Op Name: CLINTON PRODUCTION, INC.
Address: 330 NORTH ARMOUR
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4339		250 SX CMT
SURF	8.625	227		175 SX CMT

\$149 01

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2005 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: WAYNE HAMILTON Company: CLINTON PRODUCTION, INC. Phone: (316) 684-7996

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 08/17/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 5 sacks of cement on top of sand. Shot and pulled casing to 1474' and pumped 35 sacks of cement. Pulled casing to 868' and pumped 35 sacks of cement. Pulled casing to 261' and circulated 90 sacks of cement to surface.

60/40 posmix with 4% gel

Allied #20766

Perfs:

Top	Bot	Thru	Comments
3880	3884		
3870	3876		
3860	3864		
3850	3854		

**RECEIVED
KCC DISTRICT #2
AUG 25 2005
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED
DATE 8.31.05
INV. NO. 2006060407

RECEIVED
AUG 31 2005
KCC WICHITA