

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21174-00-01
Spot: W2SWNW Sec/Twnshp/Rge: 11-25S-9W
3257 feet from S Section Line, 5062 feet from E Section Line
Lease Name: TERRILL-OCHS Well #: 1
County: RENO Total Vertical Depth: 4260 feet

Operator License No.: 5585
Op Name: CLINTON PRODUCTION, INC.
Address: 330 NORTH ARMOUR
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4259		250 SX CMT
SURF	8.625	250		160 SX CMT

#138 45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2005 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: H WAYNE HAMILTON Company: CLINTON PRODUCTION, INC. Phone: (918) 642-5110

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DOUG LOUIS WitnessType: PARTIAL
Date/Time Plugging Completed: 08/15/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Plugged back 50' above perforations with 5 sacks of cement on top. Shot casing off at 2530' and pulled to 1460' with 35 sacks of cement. Pulled to 808' with 35 sacks of cement. Pulled to 300' and circulated cement to surface with 120 sacks of cement.

60/40 posmix with 4% gel

Allied #17560

Perfs:

Top	Bot	Thru	Comments
3888	3894		
3874	3882		
3856	3870		
3852	3856		

RECEIVED
KCC DISTRICT #2
AUG 18 2005
WICHITA, KS

Remarks:
Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

INVOICED
DATE 8-31-05
INV. NO. 2006060407

RECEIVED
AUG 31 2005
KCC WICHITA