

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20163-00-00
Spot: NENWNW Sec/Twnshp/Rge: 26-32S-6E
4933 feet from S Section Line, 4431 feet from E Section Line
Lease Name: LORTON EST Well #: 2
County: COWLEY Total Vertical Depth: 2915 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 510 HARDAGE CENTER 100 S. MAIN
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2915		100 SX CMT
SURF	8.625	203		160 SX CMT

\$94 74

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2005 10:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: DWAIN STOUT Company: R.R.A., INC. Phone: (316) 640-9072

Proposed
Plugging
Method:

See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 06/10/2005 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

5/2/2000 -- Sanded back 50' above perforations and dumped 5 sacks of cement. Shot casing off at 1417'. Pulled casing out of hole. Pushed plug to 300' and dumped 5 gallons of sand and 1 sack of cement.

6/1/2005 -- Rigged up and drilled plug to 350'.

6/6/2005 -- RIH with work string at 350'. Pumped 36 sacks of 60/40 posmix with 4% gel. Broke down and tagged cement at 260'.

6/10/2005 -- RIH with work string at 250'. Pumped 80 sacks of 60/40 posmix with 4% gel to surface.

116 sacks total of 60/40 posmix with 4% gel

**RECEIVED
KCC DISTRICT #2
AUG 18 2005
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed

Duane R. Krueger

(TECHNICIAN)

INVOICED
DATE 8-31-05
WT. NO. 2006060406

RECEIVED
AUG 31 2005
KCC WICHITA