

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20036-00-00

Spot: SENE

Sec/Twnshp/Rge: 19-21S-7W

3401 feet from S Section Line,

855 feet from E Section Line

Lease Name: BARBER B

Well #: 2

County: RICE

Total Vertical Depth: 3469 feet

Operator License No.: 101

Op Name: KCC FEE FUND PLUG

Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	4.5	3469		
------	-----	------	--	--

SURF	8.625	510		
------	-------	-----	--	--

300 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/16/2005 9:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: JOE MAES

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed
Plugging
Method:

See actual report.

Plugging Proposal Received By: DAVE WERTZ

WitnessType: PARTIAL

Date/Time Plugging Completed: 08/16/2005 5:00 PM

KCC Agent: DAVE WERTZ

Actual Plugging Report:

Sanded back to 3360'. Capped with 4 sacks of cement. Shot off casing at 2820'. Pulled to 1050'. Spotted 35 sacks of cement. Pulled to 650' and spotted 35 sacks of cement. Pulled to 490' and circulated cement to surface. Pulled all casing from wellbore and topped off.

195 sacks of 60/40 posmix with 4% gel

United Cement #6429

Perfs:

RECEIVED
KCC DISTRICT #2

AUG 22 2005

WICHITA, KS

Remarks: CONTROL #2005-0013-002

Plugged through: CSG

District: 02

Signed

David Wertz

(TECHNICIAN)

CC: D. WERTZ - FILE

RECEIVED

AUG 31 2005

KCC WICHITA