

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20962-00-00
Spot: NENE Sec/Twnshp/Rge: 15-34S-3E
4464 feet from S Section Line, 788 feet from E Section Line
Lease Name: METZ Well #: 1
County: COWLEY Total Vertical Depth: 3429 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3424	1520	
SURF	8.625	176	0	

111 44

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/25/2005 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2005 3:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

7/27/2005 -- Bottom plug. Pumped 30 sacks of class A 3% cc. Displaced rubber plug to 2500'. SIP 800# (39 bbls).

Allied #16356.

7/28/2005 -- Tagged cement at 2445'. Shot off 4-1/2" casing at 1420'. POOH stopping at 350'. Established circulation and pumped 150 sacks of 60/40 posmix with 4% gel to surface. Laid down 4-1/2" casing and topped off with cement.

Allied #16357

Perfs:

Top	Bot	Thru	Comments
2968	2975		
RECEIVED KCC DISTRICT #2 AUG 26 2005 WICHITA, KS			

Remarks:

Plugged through: CSG

District: 02

Signed

Duane R Krueger
(TECHNICIAN)

INVOICED
DATE 8-31-05
INV. NO. 2006060411

RECEIVED
AUG 31 2005
KCC WICHITA