

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21467-00-00  
Spot: NESENW Sec/Twnshp/Rge: 25-31S-6W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: LONG Well #: 1  
County: HARPER Total Vertical Depth: 4699 feet

Operator License No.: 32916  
Op Name: PREMIERE CORPORATION  
Address: P. O. BOX 529 22 CRESTWAY  
WELLINGTON, KS 67152

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4697		
SURF	8.625	228		

12  
\$152

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/11/2005 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/11/2005 10:30 AM KCC Agent: DAVE WERTZ

Actual Plugging Report:

Sanded back to 3700' and capped with 5 sacks of cement. Pumped 200 lbs of cotton hulls and 35 sacks of cement at 1000'. Pulled to 650' and pumped 200 lbs of cotton hulls and 35 sacks of cement. Pulled to 308' and circulated cement to surface. Pulled the rest of the 5-1/2" and topped off with 115 sacks of cement. Casing shot off at 3000'.

185 sacks of 60/40 posmix with 4% gel

Allied #20819

Perfs:

Top	Bot	Thru	Comments
3788	3794		
3748	3755		

RECEIVED  
KCC DISTRICT #2  
AUG 23 2005  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed

*David Wertz*  
(TECHNICIAN)

INVOICED

DATE

8-31-05

NO. IN

2006060414

RECEIVED

AUG 31 2005

KCC WICHITA