

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19198-00-00
Spot: NENW Sec/Twnshp/Rge: 5-34S-6E
4371 feet from S Section Line, 3355 feet from E Section Line
Lease Name: RAHN UNIT 1 Well #: 8
County: COWLEY Total Vertical Depth: 1540 feet

Operator License No.: 6679
Op Name: SHORT, W.D. AND MARJORIE D/B/A SH
Address: PO BOX 1
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	8.625	1539		200 SX CMT
SURF	13	200		225 SX CMT

50⁰⁵

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 07/27/2005 1:00 PM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 438-2856

Proposed Plugging Method: Sand back to 1063' and dump bail 10 sacks of cement. Pull 8-5/8" casing and pump cement from 300' to surface.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2005 4:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

7/11/2005 -- RIH to 450'; casing bridged.
7/13/2005 -- Circulated out sand and mud from 450' - 480'. Ran tubing to bottom; circulated well clean. Sanded back to 1060'. Dumped 10 sacks of cement on sand. Shot 8-5/8" at 805', 367', 337' and 302'. Laid down 367' of 8-5/8" casing.
7/27/2005 -- RIH to 350'; circulated and pumped 195 sacks of 60/40 posmix with 4% gel to surface.
Braden Well Plugging #05-793

Perfs:

Top	Bot	Thru	Comments
1401	1408		
1274	1282		
1157	1169		
1113	1121		

RECEIVED
KCC DISTRICT #2
AUG 19 2005
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Duane R. Krueger
(TECHNICIAN)

RECEIVED
AUG 31 2005
KCC WICHITA

INVOICED
DATE 8-31-05
INV. NO 2006060417