

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-10039-00-00
Spot: NENWNE Sec/Twnshp/Rge: 13-30S-9W
5016 feet from S Section Line, 1728 feet from E Section Line
Lease Name: GRABER B Well #: 2
County: KINGMAN Total Vertical Depth: 4313 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4310	2600	150 SX CMT
SURF	8.625	251		200 SX CMT

#140¹⁷

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/20/2005 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RANDY NEWBERRY Company: R & B OIL & GAS, INC. Phone: (620) 243-4293

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 06/21/2005 5:00 PM KCC Agent: DONALD HOBerecht

Actual Plugging Report:

Plugged back 50' above perforations with 4 sacks of cement on top. Shot casing off at 1250' with 35 sacks of cement. Pulled to 750' with 35 sacks of cement. Pulled to 300' and circulated cement to surface with 112 sacks of cement.

60/40 posmix with 4% gel

United #5272

Perfs:

Top	Bot	Thru	Comments
4264	4280		
4252	4257		
4223	4240		

RECEIVED
KCC DISTRICT #2
AUG 18 2005
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED
DATE 8.31.05
INV. NO. 2006060415

RECEIVED
AUG 31 2005
KCC WICHITA