

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23273-00-01
Spot: E2SESE Sec/Twnshp/Rge: 13-32S-4E
640 feet from S Section Line, 464 feet from E Section Line
Lease Name: MATTISON Well #: 1
County: COWLEY Total Vertical Depth: 3114 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN COURT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2050		
PROD	5.5	3070		250 SX CMT
SURF	8.625	215		

#101²¹

Well Type: SWD UIC Docket No: D23704.0 Date/Time to Plug: 08/10/2005 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL DBA MCPHERSON DRILLING CO.
Proposal Rcvd. from: DONALD BUTLER Company: DOUBLE "D" OIL COMPANY, INC. Phone: (620) 211-3570

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 08/10/2005 11:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Sanded back to 1910'. Capped with 6 sacks of cement on top of sand. Shot 5-1/2" casing at 850'. POOH with casing. RIH with tubing at 270'. Circulated and pumped 75 sacks of 60/40 posmix with 4% gel.
60/40 posmix with 4% gel
Elmores Cementing #06146

Perfs:

Top	Bot	Thru	Comments
1960	1980		
RECEIVED KCC DISTRICT #2 AUG 22 2005 WICHITA, KS			

Remarks:

Plugged through: TBG

District: 02

Signed

Duane R. Krueger

(TECHNICIAN)

INVOICED
DATE 8-31-05
INV. NO. 2006060408

RECEIVED
AUG 31 2005
KCC WICHITA