

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-02079-00-00  
Spot: N2S2NE Sec/Twnshp/Rge: 5-34S-6E  
3533 feet from S Section Line, 1319 feet from E Section Line  
Lease Name: RAHN UNIT 1 Well #: 7  
County: COWLEY Total Vertical Depth: 2925 feet

Operator License No.: 6679  
Op Name: SHORT, W.D. AND MARJORIE D/B/A SH  
Address: PO BOX 1  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	2845		200 SX CMT
PROD	4.5	2919		35 SX CMT #95 <sup>06</sup>
SURF	10.75	173		200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2005 10:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING  
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 438-2856

Proposed Plugging Method: Sand back to 2869'. Dump bail 5 sacks of cement. Pull 4-1/2" casing. Perforate 6" at 300' and pump cement to surface.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/27/2005 12:30 PM KCC Agent: DUANE KRUEGER

RECEIVED  
KCC DISTRICT #2  
AUG 19 2005  
WICHITA, KS

Actual Plugging Report:

7/1/2005 -- Sanded back to 2865'. Dumped 5 sacks of cement on sand. Shut down.  
7/5/2005 -- Shot 4-1/2" casing at 2100' and 1815'. Shut down.  
7/7/2005 -- Shot 4-12" casing at 1610' and 1410'. Laid down 1410' of 4-1/2" casing.  
7/8/2005 -- Shot 6" at 355'; could not pull out of hole. Rigged down.  
7/26/2005 -- Braden Well Plugging RIH with tubing at 350' inside of 6" casing. Circulated and pumped 50 sacks of 60/40 posmix with 4% gel to surface.  
7/27/2005 -- RIH with tubing at 350' inside of 10-3/4" and pumped 105 sacks of 60/40 posmix with 4% gel to surface.  
8/5/2005 -- Topped off plug; cement to surface.  
Braden Well Plugging #05-492

Perfs:

Remarks:

Plugged through: TBG

District: 02

Signed Duane R. Krueger  
(TECHNICIAN)

RECEIVED  
AUG 31 2005  
KCC WICHITA

INVOICED  
DATE 8-31-05  
INV. NO 2006060417

Form CP-2/3