

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-22035-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 28-33S-5E  
3686 feet from S Section Line, 1719 feet from E Section Line  
Lease Name: ANGLEMEYER Well #: 2  
County: COWLEY Total Vertical Depth: 3151 feet

Operator License No.: 6679  
Op Name: SHORT, W.D. AND MARJORIE D/B/A SH  
Address: PO BOX 1  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3199		100 SX CMT
SURF	8.625	203		85 SX CMT

41  
#102

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2005 1:00 PM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING  
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 438-2856

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/22/2005 4:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

6/2/2005 -- Sanded back to 3060'. Dumped 4 sacks of cement on sand. Shot 4-1/2" casing at 1395' and laid it down.  
6/22/2005 -- RIH with tubing at 262'. Established circulation and pumped 100 sacks of 60/40 posmix with 4% gel to surface.  
6/23/2005 -- Tagged cement at 25'. Topped back to surface.  
Braden Well Plugging #05-485

Perfs:

Top	Bot	Thru	Comments
3126	3134		
3118	3120		
3113	3115		

RECEIVED  
KCC DISTRICT #2  
AUG 18 2005  
WICHITA, KS

Remarks: OBSERVED TOP PLUG

Plugged through: TBG

District: 02

Signed Duane R. Krueger

RECEIVED  
AUG 31 2005  
KCC WICHITA

(TECHNICIAN)

INVOICED

DATE 8-31-05

WV NO 2006060417