

4-032077

7-27-95

API Number: 15-163-23,237-60-01

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NW SW NW /4 SEC. 01, 07S, 20 W  
3630 feet from S section line  
4950 feet from E section line

Operator license# 8061 Lease: Gallagher Well # 2

Operator: Oil Producers Inc. Of Kansas County: Rocks 119.93

Address: P.O. Box 8647 Well total depth 3690 feet  
Wichita, Kansas 67208 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 27 Month: July Year: 1995

Plugging proposal received from: Mike

Company: Oil Producers Inc. Of Kansas Phone:

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 01 1995  
SEP 01 1995  
CONSERVATION DIVISION  
WICHITA KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 9:00 A.M., Day: 27, Month: July, Year: 1995

Actual plugging report: 8 5/8" set at 248' cwc with 160 sxs. 5 1/2" set at 3689' with 175 sxs. Perf. At 1700' cwc with 290 sxs cement blend. Squeezed 5 1/2" with 300 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 1000#. Bled back to 200# cement at surface in annulus. Plug complete.

Remarks: Anhy. 1690' - 1720'.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 2129 GL

I did / did not observe the plugging.

Carl Goodrow  
(agent)

Form CP-2/3

INVOICED

DATE 9-6-95

INV. NO. 43408