

4-1-88

6 070659

API NUMBER 15- 163-22,993-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE NE, SEC. 1, T7 S, R 20 (W) E

4290 feet from S section line

990 feet from E section line

Lease Name HAROLD Riffe Well # 1C-2

County Rooks 119.28

Well Total Depth 3670 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 250

TECHNICIAN'S PLUGGING REPORT

Operator License # 6926

Operator: Advantage Resources Inc.
Name & Address: 1775 Sherman St. #1345
Denver, Colorado 80203
Ed Ackman

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ U&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling License Number 6033 Tag # 604

Address Wichita, Ks. 67202

Company to plug at: Hour: 8:00 AM Day: 1 Month: April Year: 19 88

Plugging proposal received from Lloyd Dellett

(company name) Murfin Drilling Inc. (phone) 303-831-1912

were: 8 5/8" - 250' S.P. cwc w/165 sks 60/40 Pozmix 2% Gel 3% Ca Cl. By Allied.

Elv. 2128'; Anhy 1700'; Arbucle at 3638'; No circulation problems. Mud condition

9.6 weight; 44 viscosity; 9.6 water loss: Proposal 225 sks 60/40 Poz 6% Gel 3% Ca Cl

and 8 5/8" plug. Spot with drill stem, recondition hole; Heavy mud between all plugs

25 sks at 3640'; 25 sks at 1710'; 100 sks at 1020' w/C.F. ; 50 sks at 300'; 10 sks at 40'.

15 sks in rat hole; (Circulate) Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:45 AM Day: 1 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Pozmix 6% Gel 3% Ca Cl and

8 5/8" plug. Spot with drill stem, recondition hole, heavy mud between all plugs.

1st plug at 3640' w/25 sks cement; 2nd plug at 1710' w/25 sks cement;

3rd plug at 1020' w/100 sks w/1 sk Celloflake; 4th plug at 300' w/50 sks cement;

5th plug Hulls, plug at 40' w/10 sks cement. (15 sks in rat hole circulate)

Remarks: Cemented by B. J. Titan (If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

DATE 5-19-88

INV. NO. 20765

Signed Marion J. Schmidt (TECHNICIAN) Marion J. Schmidt

RECEIVED STATE CORPORATION COMMISSION MAY 17, 1988 MAY 17 1988