

4-061185

5-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-22,974 -00-00

NE SW NE /4 SEC. 02, 07 S, 20 W
3630 feet from S section line
1650 feet from E section line

Operator license# 8061

Lease: Ross Well # 3

Operator: Oil Producers Inc. of Kansas

County: Rooks 119.93

Address: 2400 N. Woodlawn #115
P.O. Box 8647
Wichita, Kansas 67208-8674

Well total depth 3690 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 218 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Co Tools License# -

Address:

Company to plug at: Hour: 9:00 A.M. Day: 13 Month: May Year: 1999

Plugging proposal received from: Ted Fuchs

Company: Swift Services Phone: 785-798-2300

Were: Order 150 sxs Multidensity Cement with 500# hulls.
Went in to work on well and found deep casing leaks at 2900'.
Decided to P&A.
Emergency permission to plug with rig over hole.

RECEIVED
MAY 18 1999
11:12

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 10:30 A.M., Day: 13, Month: May, Year: 1999

Actual plugging report: 8 5/8" set to 218' w/150 sxs. 4 1/2" set to 3689' w/125 sxs.
Top stage 1750' to surface with 450 sxs. Tied onto annulus and pumped 10 sxs. Max. 500#
pressured and locked up. Tied onto production casing and pumped 140 sxs cement with 500#
hulls. Max. P.S.I. 400#. S.I.P. 200#. Waited 30 minutes. Cement at surface.

Remarks: Swift Services, Inc.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X

Plugged through TUBING, CASING Elevation: 2163 GL

I did [] / did not [X] observe the plugging.

[Signature]
OH (agent)
Form CP-2/3

INVOICED
DATE MAY 19 1999
INV. NO. 60952