

6 020528

5-8

55

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,139 - 00-00
NW NE SE, SEC. 2, T 7 S, R 20 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Operator: Oil Prod Inc. of Ks.
Name & Address: 2400 N. Woodlawn #115
Box 8647
Wichita, Ks. 67208

2310 feet from S section line

990 feet from E section line

Lease Name Wills Well # 2

County Rooks 111.48

Well Total Depth 3430 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 251 w/150 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Oil Producers Inc of Ks. License Number 8061

Address Same as above

Company to plug at: Hour: 9:30 AM Day: 8 Month: May Year: 19 90

Plugging proposal received from Jim Line

(company name) _____ (phone) 913-483-4092

were: 4 1/2" casing set at 3369' w/150 sks.

Perf 3367 to 3372. D.V. at 1700' w/375 sks. Anhy cwc.

Ordered 225 sks 60/40 poz 8% gel

Plugging Proposal Received by Gilbert Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 Day: 8 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Pumped down annulus 10 sks. Max pres. 500#. Shut in

500#. Pumped down annulus 4 1/2" 200 sks w/3 sks hulls. Max 1000. Shut in 100#.

Remarks: By Allied Cementing #5287 (If additional description is necessary, use BACK of this form.)

Should observe this plugging.

DATE MAY 22 1990

INV. NO. 28198

Signed Gilbert Balthazor (TECHNICIAN)

STATE CORPORATION COMMISSION
MAY 16 1990
CONSERVATION DIVISION
Wichita, Kansas

INVOICED