

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1977
11-15 1977
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 -179 - 20486 -00-00 (of this well)
Lease Owner K & E Petroleum, Inc.
Address 816 Union Center, Wichita, Kansas 67202
Lease (Farm Name) Sidesinger Well No. 1
Well Location C NW SW SW Sec. 36 Twp. 6 S Rge. (E) 27 (W)
County Sheridan Total Depth 4100' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin November 11, 1977, 7:45 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Gerrell Veatch Address 38 Walnut Drive, Hill City, Ks. 67642

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name K & E Petroleum, Inc.

Address 816 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge, Ass't. Sec.-Treas.
Date: November 14, 1977

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.


Dep

S. 36 T. 6 R. 27 ^{EW}

Loc. NW SW SW

County Sheridan

640 Acres
N



Locate well correctly

Elev.: Gr. 2682'

DF 2685' KB 2687'

KANSAS DRILLERS LOG

API No. 15 — 179 — 20,486 - 06 - 00
 County Number

Operator
K & E Petroleum, Inc. ad Halliburton Oil Producing Co.

Address
816 Union Center Wichita, Kansas 67202

Well No. #1 Lease Name Sidesinger

Footage Location
990 feet from (X) (S) line 330 feet from (E) (W) line

Principal Contractor Abercrombie Drilling, Inc. Geologist Don D. Strong

Spud Date November 5, 1977 Total Depth 4100' P.B.T.D.

Date Completed November 11, 1977 Oil Purchaser None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

| Purpose of string | Size hole drilled | Size casing set (in O.D.) | Weight lbs./ft. | Setting depth | Type cement | Sacks | Type and percent additives |
|-------------------|-------------------|---------------------------|-----------------|---------------|-------------|-------|----------------------------|
| Surface | 12 1/4" | 8-5/8" | 28# | 268' | Common | 190 | 2% gel 3% ca. cl. |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

LINER RECORD

| Top, ft. | Bottom, ft. | Sacks cement |
|----------|-------------|--------------|
| | | |

TUBING RECORD

| Size | Setting depth | Packer set at |
|------|---------------|---------------|
| | | |

PERFORATION RECORD

| Shots per ft. | Size & type | Depth interval |
|---------------|-------------|----------------|
| | | |
| | | |

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated

*RECEIVED
 NOV 10 1977
 CONSERVATION DIVISION
 LAWRENCE, KANSAS*

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

| RATE OF PRODUCTION PER 24 HOURS | Oil | Gas | Water | Gas-oil ratio | CFPB |
|---------------------------------|-------|-----|-------|---------------|------|
| | bbls. | MCF | bbls. | | |

Disposition of gas (vented, used on lease or sold) _____

Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator K & E Petroleum, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry

Well No. #1 Lease Name Sidesinger

S 36 T 6S R 27 K W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

| FORMATION DESCRIPTION, CONTENTS, ETC. | TOP | BOTTOM | NAME | DEPTH |
|--|------|--------|---------------------|-------|
| Surface Clay & Shale | 0 | 180 | <u>SAMPLE TOPS:</u> | |
| Sand & Shale | 180 | 257 | | |
| Shale | 257 | 918 | Anhydrite | 2379' |
| Shale & Sand | 918 | 2381 | Base/Anhy. | 2414' |
| Anhydrite | 2381 | 2415 | Topeka | 3626' |
| Shale | 2415 | 3205 | Heebner | 3836' |
| Shale & Lime | 3205 | 3995 | Toronto | 3858' |
| Lime | 3995 | 4100 | Lansing | 3877' |
| Rotary Total Depth | | 4100' | Base/K.C. | 4087' |
| | | | R.T.D. | 4100' |
| NO ELECTRIC LOG RUN: | | | | |
| DST #1 (4010'-4100') 30/30/90/60 Recovered 440' muddy water. SIP: 1112#/1007#, FP 66#-123#/148#-271# | | | | |
| DRY & ABANDONED: November 11, 1977 | | | | |

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

 Wayne L. Brinegar Signature
 Vice President Title
 November 15, 1977 Date



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

November 15, 1977

WELL PLUGGING AUTHORITY

| | |
|---------------------|----------------------------|
| Well No. | 1 |
| Lease | Sidesinger |
| Description | NW SW SW Sec. 36-6-27W |
| County | Sheridan |
| Total Depth | 4100 |
| Plugging Contractor | Abercrombie Drilling, Inc. |


K & E Petroleum, Inc.
and Halliburton Oil Prod. Co.
816 Union Center
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above
named well.