

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 179 - 2055 - 00 - 00 (of this well)
Lease Owner F & M Oil Company
Address 422 Union Center, Wichita, Kansas 67202
Lease (Farm Name) SIDESINGER Well No. 1
Well Location SW NW NE Sec. 35 Twp. 6 Rge. 27 (E) (W)
County Sheridan Total Depth 4125' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 1:00 p.m., 01-22-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 So. 2nd Street, Hill City, KS

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to

Name F & M Oil Company

Address 422 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent

Date: January 29, 1980

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1980
01-31-1980

15-179-20551-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	F & M Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Sidesinger #1
LOCATION:	SW NW NE, Section 35-6-27 Sheridan County, Kansas
SPUD DATE:	January 15, 1980
COMPLETION DATE:	January 22, 1980

0	310	Surface clay sand and shale
310	372	Sand and shale
372	2402	Shale
2402	2436	Anhydrite
2436	2695	Shale
2695	3604	Shale and lime
3604	4125	Lime
	4125	Rotary Total Depth

Spud hole at 11:45 a.m., January 15, 1980. Drilled 372' of 12 1/4" hole. Ran 9 joints of 8-5/8" used 28# casing. (Talley 363.97'). Set at 371' with 265 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 7:15 p.m., January 15, 1980.

T.D. 4125'. Set 1st plug at 1400' with 70 sacks, 2nd plug at 360' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks and rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 1:00 p.m., January 22, 1980.

SAMPLE TOPS:

Anhydrite	2402'
B/Anhydrite	2436'

RECEIVED
STATE OIL & GAS COMMISSION

JAN 3 1980

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

CONSERVATION DIVISION
Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Sidesinger #1, SW NW NE, Section 35-6-27, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid as of this 29th day of January, 1980.



Sherrie L. Brooks
Sherrie Brooks, Notary Public

My commission expires 08-21-82.

State of Kansas



15-179-20551-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY

Governor
Chairman
Commissioner
Commissioner

Carol J. Larson, Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

January 28, 1980

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Sidesinger
Description	SW NW NE
Section	Sec. 35-6S-27W
County	Sheridan
Total Depth	4125'
Plugging Contractor	Abercrombie Drilling, Inc.


F & M Oil Co., Inc.
422 Union Center
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,


J. LEWIS BROCK, Administrator

~~Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657~~
is hereby assigned to supervise the plugging of the above named well