

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

15-179-05165-00-00

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner EMPIRE DRILLING COMPANY Address 400 BROWN BUILDING, WICHITA 2, KANSAS
(Applicant)

Lease (Farm Name) MUIR Well No. 1

Well Location NE NE NE Sec. 13 Twp. 6S Rge. 27 (E) W (W)

County SHERIDAN Field Name (if any) _____

Total Depth 3752' Oil ___ Gas ___ Dry Hole X

Was well log filed with application? YES If not, explain: _____

Date and hour plugging is desired to begin FEBRUARY 13, 1956

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner _____

MARION C. HELBERG Address 811 NORTH JONES, NORTON, KANSAS

Plugging Contractor EMPIRE DRILLING COMPANY

Plugging Contractor's Licence No. NONE REQUIRED - ROTARY DRILLED HOLE

Address 400 BROWN BUILDING, WICHITA 2, KANSAS

Invoice covering assessment for plugging this well should be sent to _____

EMPIRE DRILLING COMPANY Address 400 BROWN BUILDING, WICHITA 2, KANSAS

and payment will be guaranteed by applicant.

EMPIRE DRILLING COMPANY
BY: DAN J. KORNFELD

[Signature]
Applicant or Acting Agent

Date FEBRUARY 16, 1956

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1956
02-23-1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 13 T 6 R 27 W
BOOK PAGE 39 LINE 45

15-179-05165-00-00

L O G

COMPANY: EMPIRE DRILLING COMPANY
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM: MUIR No. 1
 LOCATION: NE NE NE, SEC. 13-6S-27W,
 SHERIDAN COUNTY, KANSAS
 COMMENCED: 2-4-56
 COMPLETED: 2-13-56

0	TO	375	SURFACE SHALE AND SAND
375	TO	1062	SHALE
1062	TO	1263	SHALE AND SHELLS
1263	TO	1500	PYRITE, SHALE AND SHELLS
1500	TO	1915	SHALE AND SAND
1915	TO	2111	SHALE AND SHELLS
2111	TO	2145	ANHYDRITE
2145	TO	2640	SHALE AND SHELLS
2640	TO	3620	SHALE AND LIME
3620	TO	3752	LIME
3752			R.T.D.

SET 8 5/8" SURFACE CASING AT 345', CEMENTED WITH 160 SACKS OF CEMENT.

ELEVATION: 2569 K.B.

TOPS: ANHYDRITE 2111'; HEEBNER 3530'; TORONTO 3535'; LANSING 3572'; R.T.D. 3752'.

D.S.T. #1 3638 TO 3655'; D.S.T. #2 3742 TO 3752'.

D & A

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE MUIR NO. 1, NE NE NE, SECTION 13, TOWNSHIP 6 SOUTH, RANGE 27 WEST, SHERIDAN COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 16TH DAY OF FEBRUARY, 1956.

MY COMMISSION EXPIRES JUNE 7, 1956

Charlotte Kletchka
 NOTARY PUBLIC
 CHARLOTTE KLETCHKA

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
 FILE SEC 13 T 6 R 27 W
 BOOK PAGE 39 LINE 45



15-179-05165-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

February 20, 1956

Well No.	1
Lease	Hair
Description	NE NE NE 13-6-27N
County	Sheridan
File No.	39-15

Empire Drilling Company
1121 Union National Bank Bldg.
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

By S. S. Greider

S. S. Greider
WELL PLUGGING SUPERVISOR

cc:
District Plugging Supervisor