


15-163-19072-00-00
20158-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Flat

Rooks _____ County. Sec. 18 Twp. 7 Rge. 16 (E) _____ (W) _____
Location as "NE/CNW/SW" or footage from lines. SW SW NW
Lease Owner Strata Drilling Company
Lease Name Melton Well No. 1
Office Address 2421 Tenth Street, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Plugged surface pipe
Date well completed _____ 12-2 19 68
Application for plugging filed _____ 12-2 19 68
Application for plugging approved _____ 12-2 19 68
Plugging commenced _____ 12-2 19 68
Plugging completed _____ 12-2 19 68
Reason for abandonment of well or producing formation Water Loss on first location.

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1127 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	252'	


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1127 - CL Surface filled with heavy mud (14#) to hold flow.
100 sacks common cement with 6% Gel through swedge on top. Plug pumped down 250# by Halliburton

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1969
CONSERVATION DIVISION
Wichita, Kansas

1-2-69

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Peel Brothers, Inc.
Address Box 359, Hoisington, Kansas 67544



STATE OF Kansas, COUNTY OF Barton, ss.
Peel Brothers, Inc. (employee of owner) _____ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed and that the same are true and correct. So help me God.
(Signature) Wendell C. Peel
Wendell C. Peel, President
(Address) _____

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 68
My commission expires 6-21-70
Ethel S. Williamson
Ethel S. Williamson Notary Public.

15-163-~~14072-00-00~~
20158-00-00

DRILLER'S LOG

Well Owner: Strata Drilling Company
Farm Name: Melton #1
Date Started: 11-29-68
Date Completed: First Location 12-2-68
Second Location 12-14-68
Total Depth: 3280 feet

SW SW NW
Section 18-7S-16W

Casing: 8-5/8" set at 252' cemented - first location
8-5/8" set at 1114' cemented - second location

Contractor: Peel Brothers, Inc.

Bottoms of formations are as follows -

1st Location -	Clay	0 - 40
	Shale and Sand	660
	Sand	795
	Shale	1060
	Red Bed	1110
	Anhydrite	1127
2nd Location -	Surface Shale	0 - 365
	Shale	910
	Shale and Red Bed	1109
	Anhydrite	1142
	Shale and Shells	1490
	Lime and Shale	2473
	Shale and Lime	3210
	Lime	3280
	Total Depth	3280

This is to certify that the above information is true and correct to the best of our knowledge.

PEEL BROTHERS, INC.

Wendell G. Peel
Wendell G. Peel
President

SUBSCRIBED AND SWORN to before me this 30th day of December, 1968.



Ethel S. Williamson
Ethel S. Williamson
Notary Public

My Commission expires 6-21-70

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1969
CONSERVATION DIVISION
Wichita, Kansas
1-2-69