

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION RECEIVED
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
 K.A.R. 82-3-117

RECEIVED
AUG 26 2005
KCC WICHITA

Form CP-4
 December 2003
 Type or Print on this Form
 Form must be Signed
 All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.
 Address: 250 N. Water, Suite 300
 Phone: (316) 267-3241 Operator License #: 30606
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 5/27/05 (Date)
 by: David Williams (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
4230-38, 4268-78, 4308-17 Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 153-00036-00-01
 Lease Name: Texaco Cahoj Unit
 Well Number: #50
 Spot Location (QQQQ): SE - SE - SE -
 _____ Feet from North / South Section Line
 _____ Feet from East / West Section Line
 Sec. 18 Twp. 1 S. R. 34 East West
 County: Rawlins
 Date Well Completed: 6/59
 Plugging Commenced: 8/18/05
 Plugging Completed: 8/18/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	446	8 5/8	446	0
	Production	Surface	4761	5 1/2	4761	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Tubing @ 2480', CIBP @ 4068', FL @ 1200' FS. RU Swift. Pumped 125 sx SMD cmt & 400# hulls. Gained circ w/35 bbls.
Pulled tbg to 1200'. Pumped 40 sx same & 275# hulls. Circ cement to surface. TOH w/tbg. Installed 5 1/2" swage. Pumped 16 sx & press to 300# & held. SI. Hooked up to 8 5/8". Pumped 4 sx & fld coming out of csg hanging. To top off when 8 5/8" & 5 1/2" csg is cut off.
Job complete @ 11:20 am. Witnessed by Darrel Dipman w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
 Address: 250 N. Water, Suite 300 ; Wichita, KS 67202
 Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.
 State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 25th day of August, 2005.

Susan Brady My Commission Expires: 11-4-07
 Notary Public

[Handwritten signature]