

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
AUG 26 2005

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: Palomino Petroleum, Inc.

Address: 4924 SE 84th St., Newton, Ks. 67114-8827

Phone: (316) 799-1000 Operator License #: 30742

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: August 17, 2005 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 3059' Bottom: 3378' T.D. 3385'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-NA-009-02109-00-00

Lease Name: Lureman Luerman

Well Number: #1

Spot Location (QQQQ): _____ - SE / _____ - NW - SE

_____ Feet from ☐ North / ☐ South Section Line

_____ Feet from ☐ East / ☐ West Section Line

Sec. 18 Twp. 16 S. R. 13 ☐ East ☒ West

County: Barton

Date Well Completed: 06/26/1945

Plugging Commenced: August 19th, 2005

Plugging Completed: August 23rd, 2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	160'	10"	160'	0'
	Production	0'	3378'	5-1/2"	3378'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Sand off bottom and put 5 sacks of cement on top of sand. Loaded hole with water. Spot in casing jacks. Worked casing to get slips out of head.

Got 300' of free pipe. Pulled casing jacks off. Rigged up Perf-Tech. Went in casing - shot holes at 1625' - 900' - 525'. Trip in hole with tubing to 1600'. Hooked

up to pump cement. Pumped 55 sks - 200# hulls. Pulled up to 900' - pumped 30 sks - 300# hulls. Pulled up to 525' - pumped 15 sks cement. Went

on vacuum. Allied went back for 250 sks - 800# hulls. Rigged down and moved off.

Name of Plugging Contractor: D. S. & W. Well Servicing, Inc License #: 6901

Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: Palomino Petroleum, Inc.

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 25th day of August, 20 05

Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202