

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-00216-0000

LEASE NAME BLAKE

WELL NUMBER 1-18

2540' FNL Ft. from S Section Line

2540' FWL Ft. from E Section Line

SEC. 18 TWP. 30S RGE. 36W (E) or (W)

COUNTY GRANT

Date Well Completed 5/11/46

Plugging Commenced 8/22/05

Plugging Completed 8/22/05

RECEIVED

AUG 29 2005

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to GORS. Div.
office within 30 days

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (972) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/20/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 3008' GL Bottom 2733' T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2396'	2706'	10 3/4"	583'	0
				7"	2742'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

8/22/05 P&A witnessed by J Holland. Set CIBP @2300' KB, spot 20' cmt, Revise PBTD @2280'. TOC@140'. NU cmtr.load hole w/24 ppg 36cp mud & 25 sx cmt 1650'-1525'. Pmp 35 bbl mud 1525'-600' & 35 sx cmt plug 600'-425' & 14 bbl mud to 40'. Pump 10 sx cmt 40'-0', NU cmt to 10-5/8" surf. Pmp 35 sx cmt 140'-0'. Cut 7" csg & 10 3/4" csg 3' bgl, weld on trash cover-ID plate.


Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 26th day of August, 20 05

My Commission Expires: 7/14/2009 Notary Public