

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-00500-0000 01

LEASE NAME TRUESDALE

WELL NUMBER 1-12

2540' FNL Ft. from S Section Line

2540' FWL Ft. from E Section Line

SEC. 12 TWP. 30S RGE. 35W (E) or (W)

COUNTY GRANT

Date Well Completed 1940 4-20-1962

Plugging Commenced 8/22/05

Plugging Completed 8/24/05

RECEIVED

AUG 29 2005

KCC WICHITA

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (727) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/20/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2986' GL Bottom 2742' T.D. 2742'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2512'	2692'	10 3/4"	586'	0'
				7"	2519'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

P&A witnessed by J Holland. NU cmtr. Pmp 500# cottonseed hulls w/10 bbl mud + 40 sx cmt 2512'-2312'. Load csg w/8 bbl mud & 25 sx cmt 1700'-1575'. Pmp 62 bbl mud to 0'. NU cmtr to 7" csg, load & circ hole w/55 bbl mud & 75 sx cmt 610'-460'. Disp w/17 bbl mud. Load hole to 40' w/9 bbl mud. Pmp 22 sx cmt 40'-0'. Cut 7" csg & 10 3/4" csg 3' bgl, weld on trash cover, ID plate.


Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God



(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 26th day of August, 20 05

My Commission Expires: 7/14/2009
Angie A. Hernandez
Notary Public