

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22759-00-~~W01~~
Spot: CNENESW Sec/Twnshp/Rge: 3-7S-20W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: PROBASCO Well Number: 2-1
County: ROOKS Total Vertical Depth: 3673 feet

Operator License No.: 5011
Operator Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202 *9/11*

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 345
Production: Size 4.5 feet: 3672 *119.37*
Liner: Size feet:

Well Type: EOR UIC Docket No: E-25885 Date/Time to Plug: 9/11/00 11:00:00 AM

Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC

Proposal Rcvd. from: JAMES B. DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed 4 1/2" casing set at 3672' w/125 sxs cmt.
Plugging D.V. Anhy @ 1765' w/450 sxs.
Method: Ordered 150 sxs 60/40 pozmix - 10% gel - 15 sxs gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 09/11/2000 2:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 4 1/2" casing and squeezed as follows:
50 sxs cmt plus 500# hulls, followed with 15 sxs of gel, followed with 80 sxs cmt. Max. P.S.I. 900#. S.I.P. 800#.
Rigged up cementers 8 5/8" S.P. Pressured up to 600#. Job complete.

Rec'd
09-22-00
RECEIVED
STATE CORPORATION COMMISSION
SEP 22 2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: THIS WELL WAS FORMERLY KNOWN AS ROSS A-1.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 9/25/00

INV. NO. 2001060730

Form CP-2/3

SEP 18 2000

THUNDERBIRD DRILLING, INC.

P.O. BOX 18407

WICHITA, KS. 67218

CONTR COMPANY TOOLS

GEOLOGICAL MARK THOMPSON


#1 ROSS 'A'

CTY ROOKS

FIELD PROBASCO

3-7-20W
NE NE SW

ELV 2193 KB SPD 9/23/85 CARD ISSUED 10/31/85 IP P 40 BOPD, NW
LKC 3567-3574



| LOG | Tops | Depth/Datum | API 15-163-22,759 |
|-------|------------|-------------|---|
| ANH | 1760+ | 433 | 8 5/8 " 345 / 225SX, 4 1/2 " 3672 / 125SX, MULTI STAGE COLLAR AT 1765 / 450SX |
| B/ANH | 1794+ | 399 | DST (1) 3407-3430 (LANS) / 30-30-30-30, REC 20' OIL SPTD M, SIP 704-695#, FP 28-38# |
| TOP | 3175- | 982 | DST (2) 3438-3475 (LANS) / 30-45-60-45, REC 5' OIL SPTD M, 345' MW, SIP 933-915#, FP 28-174# |
| HEEB | 3381- | 1188 | DST (3) 3482-3520 (LKC) / 30-45-30-45, REC 2' MDY OIL, 120' MW, SIP 455-450#, FP 28-78# |
| LANS | 3417- | 1224 | DST (4) 3559-3590 (LKC) / 30-45-60-45, 300' GIP, REC 280' GSY OIL, 120' GSY MDY OIL, SIP 532-455#, FP 48-184# |
| BKC | 3620- | 1427 | DST (5) 3655-3671 (ARB) / 30-30-30-30, REC 40' MW, SIP 701-574#, FP 19-35# |
| ARB | 3666- | 1473 | MICT - CO, PF (LKC) 3567-3574 & 3582-90, SWB DWN, AC 500G & 38 BALL SEALERS, SWB DWN & TST 10 BOPH, NW, FU 600' OIL, SWB 13 BOPH, T&R, POP, P 40 BOPD, NW, 10/14/85 |
| RTD | 3671- | 1478 | |
| LTD | 3675- | 1482 | |

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS